



# PARTS LIST

P.O. Box 38-828  
PETONE, Wellington  
Phone - (64-4) 9393 777  
\* \* \* \* \*

Date - 12th April, 2003

e-mail = sales@casa.co.nz

Ref - PART-LST.FRP

Record:- 14 Date:- 7 Apr 03 Time:- 10:03 AM Data File Ref :- D:\FORMS\CASA\PARTSLST\PARTSLST.DBF

## KIT of Parts

NOTE :- Upon opening this KIT, please confirm the presence of all parts and tick the Receiver's "CHK" box.

### CASA KIT Part Number :-

# CON-28Ux650-MDF18-14U-CBV

### Product Description:-

*Rack Console 28U x 650mm deep with 1 bay of 14U RA393 extrusion, 1 Vanity Panel, 500mm Desk, Tie-Panel (optional) and/or Duplex RA393 (when appropriate)*

Item	Part Number	Description	Qty	Net Kg per piece	CHK
1	RA393-14U-AL8A-4SH(M5)	Rack Angles - 14U (pre-drilled) with 4 x M5 side fixing holes	2		
2	TPA-524x503-MDF18...	Top panel Assembly 524x503mm for Consoles & Racks	1		
3	BA-650x488x98-MDF18...	Base Assembly for 650mm deep Rack & Consoles	1		
4	TB-1Ux488x71-MDF18...	Tie-Bar for lateral support within Wooden Racks & Consoles	1		
5	CLT-507x50-MDF18...(DSK)	Cleat for Desk Fixing within Wooden Racks & Consoles	2		
6	DT-524x500-MDF30...	Desk Top for Wooden racks & Consoles	1		
7	PNLA-14Ux488-MDF18...	Vanity or Dummy Panel Assy for Wooden racks & Consoles	1		
8	CSP-28Ux650-MDF18...	Console Side Panel for 28U x 650mm deep Rack Consoles	2		
	<b>DUPLEX - OPTION</b>	For Consols joined to other consoles or racks the use of the RA393 with 4 x 5mm counterbored clearance holes is required & the alternative DUPLEX Hardware Kit is needed In this situation SUITES will require substitution of item 9			
9	RA393-14U-AL8A-4CH(5mm)	Rack Angles - 14U (pre-drilled) with 4 x 5mm side clearance holes with counterboring to suit M5 socket-head cap screws			
	<b>ADDITIONAL-OPTIONS</b>	Up to 4 x PNLA-14Ux488-MDF18.... panels may be fitted 2 x TB-1Ux488x71-MDF18...are recommended for Racks			
13	HWK-CON-MDF18-Duplex	Hardware Kit for SINGLE - stand-alone Rack Consoles			
14	INST-CONSOLE-MDF18	Instructions/Drawing for ASSEMBLY of MDF consoles	1		

### Summary :-

This product has been manufactured under CASA's Quality Assurance Scheme.

Total PIECES	12
Total PACKAGES	
Total Line ITEMS	11
GROSS Weight Kg	0.0

<b>Packed by:-</b>	
<b>Date packed:-</b>	
<b>Date Checked:-</b>	

D:\FORMS\CASA\PARTSLST\PART-LST.FRPSat Apr 12 2003 10:16:42

